

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,

Wichita, Kansas

23-16-12W


Company- THE CARL TODD DRLG. CO. et al
Farm- Riemann No. 2

SEC. 23 T. 16 R. 12W
SE NE NW

Total Depth. 3369
Comm. 10-10-51
Shot or Treated.
Contractor.
Issued. 12-22-51

Comp. 10-23-51

County Barton
KANSAS



CASING:

8 5/8" 200' cem. w/125 sx
5 1/2" 3359' cem. w/100 sx

Elevation. 1923 DF
(1925 land)
Production. Pmp. 35 bbls.

Figures Indicate Bottom of Formations.

surface clay, rock	75
shale, shells	250
shale, red bed	350
shale, sand	530
shale, shells	815
anhydrite	835
shale, red bed	900
shale, shells	1190
shale, salt	1345
shale, shells	1530
shale, lime	1670
lime	1735
lime, shale	2765
lime	2970
shale, lime	3087
lime	3155
lime, shale	3185
lime	3358
sand,	3362 RTD
sooy sand	3369
Total Depth	

Tops: R.B.	
Topeka	2674
Heebner	2994
Brown Lansing	3086
Sooy Sand	3358