

State Kansas County Kiowa

Company Gramehart-Miller Oil Co. Well No. 1


Farm Douglas

Survey

Block No. Sec. 36 Twp. 29S Range 16W

Co-Ord. C.P. 4400-50 S.P. 4550 Elev. 1978 KB

NE NE NE Rig #3 1973 Gr



5/8-Chicago Group  
 3/8-Gramehart-Miller Oil Co.  
 DHM:  
 Lion Oil Co. - \$3500  
 J, S & F - \$4000  
 GMR-M & Newmont, et al-\$4000  
 (Cyprus & Voorhees)

Geol: Vernon Hess

NOTE: Show Sketch of Lease and Well Location in Above Space

330 Ft. from N. Line Ft. from S. Line

Ft. from W. Line 330 Ft. from E. Line

Date	Depth	SPD 3-3-56
3-5		8 5/8" @ 230' w/200 sx cem, 4 gel, 4 c.c. PD 6:25 am 3-4-56
		Repairing Jack Shaft. Should be ready to go this evening.
3-6	565	Drlg S.U.S. 4:15 a.m.
3-7	1840	Drlg
3-8	2364	Drlg
3-9	2712	Drlg
3-10	3157	Drlg

702574

Date	Depth	
3-12	3922	Heebner (-1944)
	3956	Douglas (-1978)
	3957	Drlg
3-13	4080	Brown Lime (-2102)
	4098	Lansing (-2120)
	4175	Drlg
3-14	4319	Drlg (1° off 4225)
3-15	4463	Drlg
3-16	4510	Base/K.C. (-2532)
	4532	Marmaton (-2554)
	4600	Miss Chert (-2622)
		4612-25 course vug por & S.S.O
		Taking DST 4605-25
3-17	DST #1 4605-25,	op 1 hr 15", cl 20".
		V. wk bl for 15". Rec 30'
		v. sli o&gcm. IF&FF-80, BHP-110
	4684	Making bit trip
3-19	4705	Viola (-2727)
	4755	R.T.D. Ran Sj Laterolog
		D&A Plugging Completed
		11:30 p.m. 3-18-56