


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - DEEP ROCK OIL CORP.
Farm - L.W. Robinson No. 52.

SEC. 16 T. 25 R. 5 E
NE SW NW SE
859'S 457'E NWc SE

Total Depth. 2512½'
Comm. 9-23-44 Comp. 10-16-44
Shot or Treated.
Contractor. Rex & Morris Drlg. Co.
Issued. 12-23-44

County. Butler
KANSAS



CASING:
16" 105' 85/8" 1825' P
13" 790' P 7" 2510' 6" Cem.
10¾" 1545' P

Elevation. _____
Production. Pmp 100 B.

Figures Indicate Bottom of Formations.

soil	0-5	lime	1010	shale gry	
lime	40	shale	1075	Chattanooga	2511
shale	60	lime	1105	Viola wh chert &	
lime (3 BWPH 90-105)	105	shale	1130	dolomite sat	2512½
shale	115	lime	1140	Total Depth	
lime	125	shale	1150		
shale	150	lime	1180		
lime	165	shale	1195	Viola Lime	2511-2512½
shale	170	lime	1205		
lime	195	shale	1210		
2½ BW 185-95		lime	1235	10-17-44 Acidized w/500 gal,	
shale	200	lime	1320	flushed w/15 BW - thru csg.	
red rock	205	1½ BW 1300-10		Made ¼ BO ¼ BW before acid	
shale	220	shale	1370	Made 82 BO 32 BW after acid	
lime	230	lime	1415		
shale	240	shale	1420		
lime	260	lime	1435		
shale	270	shale	1485		
lime	285	shale sdy	1510		
shale	325	sand wtr	1520		
lime	330	6 BWPH 1510-20			
shale	355	shale	1545		
lime	375	shale sdy	1580		
shale	415	shale	1600		
lime	420	lime	1605		
shale	430	shale	1630		
lime	450	lime	1640		
shale	455	shale	1695		
lime	460	lime	1780		
shale	475	1 BWPH 1735-45			
lime	485	Smell oil 1735			
shale	495	sand wtr	1795		
lime	505	HFW 1780-95			
shale	580	lime	1850		
shale & shells	600	sand wtr	1865		
shale	610	HFW 1850-65			
lime	615	shale sdy	1870		
shale	625	shale	2005		
lime	630	1 BWPH 1980			
shale	640	lime	2125		
sand sm-ll show of		shale	2130		
oil	650	lime	2140		
shale	675	shale	2155		
shale sdy	695	lime	2160		
2 BW 675-695		shale	2235		
Little more oil		lime	2245		
show w/wtr		shale	2280		
shale	740	show oil	2280		
lime	745	lime	2290		
shale	790	shale	2325		
lime	795	lime	2370		
shale	805	shale	2434		
lime brkn	820	lime	2441		
lime	875	shale	2450		
shale	960	lime	2453		
shale & shells	975	shale	2487		
lime	990	lime	2489		
shale	1000				