


8-25-5E

CITIES SERVICE OIL CO.  
Wilson No. 205

SEC.8 T.25 R.5 E  
SE NE SW  
990'S 330'W Cen.Sec.

Total Depth. 1971'  
Comm. 9-15-41 Comp. 9-25-41  
Shot or Treated. 2000 Gals.  
Contractor. Sharon Drlg.Co., Inc.  
Issued. 11-22-41

County. Butler



CASING:  
4 1/2" 1946' Cem.

Elevation.

Production. 201 BO, 10 BW

Figures Indicate Bottom of Formations.

surface	2
lime	35
shale & lime	85
lime brkn	495
shale lime	809
cored	848
lime & shale	1470
cored	1512
shale	1665
lime	1687
core	1735
lime	1820
shale	1938
lime	1971
Total Depth.	

Top Burlingame lime 798  
show oil 806-15, 824-37

sand 1463-75; 1493-1502  
show oil

Top Lansing 1663  
show oil 1683-1737

Top Kansas City 1939  
pay 1951-63