

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bldg., Wichita, Kansas


15-16-12W

Company - VICKERS PETRO. CO., INC.  
Farm - Ehly No. 3

SEC. 15 T. 16 R. 12 W  
SW SE SW

Total Depth. 3369'  
Comm. 4-8-47 Comp. 4-27-47  
Shot or Treated.  
Contractor.  
Issued. 5-17-47

County. Barton  
KANSAS



Elevation. 1908 *set # rh*

Production. Dry

CASING:

8 5/8" 502' Cem. w/140 sx.  
5 1/2" 3364' Cem. w/90 sx.

Figures Indicate Bottom of Formations.

shale & lime	0-180
sand	220
shale & shells	310
sand & shale	450
shale	502
shale & shells	610
red bed	795
anhydrite, sdy	825
shale & red bed	860
shale	945
shale & shells	1180
salt & shale	1190
salt	1380
shale & shells	1470
shale	1500
lime	1520
shale & lime	1570
lime brkn	1870
shale & lime	1910
lime brkn	1990
lime	2140
lime & shale	2190
shale & shells	2388
shale & lime	2625
lime & brkn shale	2710
lime brkn	2780
lime & shale	3035
shale	3075
lime	3345
shale, sand	
conglomerate	3363
lime Arbuckle	3367
Rot. T. D.	
lime Arbuckle	3369
Total Depth.	

Tops:

✓ casing 3072 DF  
Arbuckle 3363 DF

Well drld in w/cable tools  
from 3367-39' TD. Perf. 28 shots  
3172-84'. Acidize w/500 gals. - wtr.