

# Cherokee Wells, LLC

4916 Camp Bowie Blvd. Ste. 200 - Fort Worth, TX 76107

Contractor License # 33539

817-546-0034/ TX Office; 817-296-6541/Jens Hansen Cell; 817-624-1374/FAX

620-839-5581/ KS Office; 620-432-6170/Jeff Kephart Cell; 620-839-5582/FAX

KCC  
MAR 27 2006  
CONFIDENTIAL

Rig #:	CW	Lic 33342	S 33	T 28S	R 14E			
API #:	15-205-26193-00-00		Location: NW4, SW4, NE4					
Operator:	Blue Jay Operating LLC		County: Wilson					
4916 Camp Bowie Suite 204			<b>Gas Tests</b>					
Fort Worth, TX 76107								
Well #:	A-3	Lease Name: Lisher	Depth	Pounds	Orifice	flow - MCF		
Location:	1650	ft. from N Line	830	1	3/8"	19		
	2310	ft. from E Line	955	3	3/8"	33.5		
Spud Date:	1/26/2006		1030	Gas Check Same				
Date Completed:	1/27/2006	TD: 1302	1105	2	3/8"	27		
Driller:	Jeff Thompson		1242	Gas Check Same				
<b>Casing Record</b>	<b>Surface</b>	<b>Production</b>						
Hole Size	11 1/4"	6 3/4"						
Casing Size	8 5/8"							
Weight	26#							
Setting Depth	43'							
Cement Type	Portland							
Sacks	10							
Feet of Casing	43' 5"							
Rig Time	Work Performed							
Well Log								
Top	Bottom	Formation	Top	Bottom	Formation	Top	Bottom	Formation
0	6	OB	576	583	lime	877	911	shale
6	174	shale	583	588	shale	911	927	Oswego lime
174	178	lime	588	670	lime			Oil
178	252	shale	670	728	shale	927	933	Summit
252	268	lime	728	741	sand	933	940	lime
268	277	shale			No Show	940	948	Mulky
277	328	lime	741	800	shale	948	954	lime
328	331	shale	800	826	sand	954	991	shale
331	373	sand			No Show	991	1003	sand
		No Show	826	845	sand/ shale			No Show
373	429	sand/ shale	845	849	lime	1003	1018	sand/ shale
400		Added Water	849	851	shale	1018	1019	coal
429	521	lime	851	852	coal	1019	1078	sand/ shale
521	536	shale	852	854	shale	1078	1079	coal
536	576	sand	854	877	Pink lime	1079	1095	shale
		No Show			Oil	1095	1096	coal

RECEIVED  
APR 24 2006

KCC WICHITA

