

Well Refined Drilling Company, Inc.

4270 Gray Road - Thayer, KS 66776

Contractor License # 33072 - FEIN # 48-1248553

620-763-2619/Homer 620-432-6170/Jeff's Pocket; 620-423-0302/Truck 620-763-2065/FAX

Rig #:	3		S 7	T 31	R 18
API #:	15-099-23635-0000		Location NE, SE		
Operator:	Quest Cherokee, LLC		County: Labette		
Address:	PO Box 100				

Address: PO Box 100 Benedict, KS 66714				Gas Tests		
Well #:	7-4	Lease Name: Phillips, R. Dale		Depth	Oz.	Office flow - MCF
Location:	1980	ft. from (N / S)	Line	505	No Flow	
	530	ft. from (E / W)	Line	525	4"	3/8" 7.14
Spud Date:	9/27/2004			545	Gas Check Same	
Date Completed:	9/28/2004 TD: 1045			605	Gas Check Same	
Geologist:				645	Gas Check Same	
Casing Record.	Surface	Production		665	Gas Check Same	
Hole Size	12 1/4"	6 3/4"		785	Gas Check Same	
Casing Size	8 5/8"			945	Gas Check Same	
Weight				994	7"	1/2" 16.7
Setting Depth	21' 5"			1005	6"	1/2" 15.4
Cement Type	Portland					
Sacks	4	W				
Feet of Casing	21' 5"	C				
Rig Time	Work Performed					

Well Log

Top	Bottom	Formation	Top	Bottom	Formation	Top	Bottom	Formation
0	2	Overburden	475	478	shale	603	635	shale
2	6	clay	478	501	Pink lime	635	636' 6"	Bevier coal
6	12	shale	501	503	shale	636' 6"	653	shale
12	57	lime	503	507	Lexington blk shale	653	655	lime
57	128	shale	507	525	shale	655	656	shale
128	159	lime	525	527	coal	656	658	blk shale
159	211	shale	527	536	shale	658	659	Croweburg coal
211	214	lime	536	538	coal	659	713	shale
214	248	shale	538	558	shale	713	714	coal
248	252	lime	558	560	lime	714	770	shale
252	278	shale	560	569	shale	770	773	blk shale
278	330	lime	569	572	Summit blk shale	773	774	Weir coal
330	334	shale	572	592	Oswego lime	774	791	shale
334	343	lime	592	593	shale	791	792	coal
343	368	shale	593	597	Mulky blk shale	792	813	shale
368	394	sand	597	598	coal	813	814	coal
394	474	shale	598	603	lime	814	876	shale
474	475	coal	600	603	oil show	876	893	laminated sand

RECEIVED
CONSERVATION COMMISSION

APR 13 2006

CONSERVATION DIVISION
WICHITA, KS

