

Air Drilling
Specialist
Oil and Gas Wells



M.O.K.A.T. DRILLING
Office Phone: (620) 879-5377



P.O. Box 590
Caney, KS 67333

Operator QUEST CHEROKEE LLC.		Well No. 8-1	Lease MYERS	Loc. 1/4 1/4 1/4	Sec. 8	Twp. 31	Rge. 18					
County LABETTE		State KS	Type/Well	Depth 1038'	Hours	Date Started 100-08-04	Date Completed 10-11-04					
Job No.	Casing Used 21' 6" OF 8 5/8"	Bit Record			Coring Record							
Driller BILLY	Cement Used	Bit No.	Type	size	From	To	Bit No.	type	Size	From	To	% Rec.
Driller	Rig No. 2			6 3/4"								
Driller	Hammer No.											

Formation Record

From	To	Formation	From	To	Formation	From	To	Formation	From	To	Formation
0	2	DIRT	547	550	SHALE (SUMMIT)	790	848	SAND			
2	40	LIME	550	557	BLACK SHALE	848	902	SHALE			
40	70	SANDY SHALE	557	572	LIME	863		GAS TEST SAME			
70	109	SAND	562		GAS TEST 3# 1/8"	902	917	SAND			
109	145	LIME	572	577	BLACK SHALE (MULKEY)	917	918	COAL (ROWE)			
145	170	SHALE	577	578	COAL	918	927	SHALE			
170	171	COAL	578	579	SHALE	927	928	COAL (NEUTRAL)			
171	197	SHALE	579	580	LIME	928	973	SHALE			
197	200	LIME	580	590	SAND	938		GAS TEST SAME			
200	217	BLACK SHALE (DAMP)	587		GAS TEST 18# 3/8"	973	984	SAND			
217	219	LIME	590	630	SHALE	984	985	COAL (RIVERTON)			
219	220	SHALE	630	631	COAL (BEVIER)	985	989	SHALE			
220	222	LIME	631	647	SHALE	988		GAS TEST			
222	227	BLACK SHALE	637		GAS TEST 8# 1/2	989	1015	CHAT LIME (MISSISSIPPI)			
227	262	SANDY SHALE	647	648	LIME	1015	1024	GREY LIME			
262	285	LIME (DAMP)	648	650	SHALE	1024	1038	BROWN LIME			
285	290	LIMEY SHALE	650	651	COAL (CROWBERG)	1038		GAS TEST 10# 1/2"			
290	301	SHALE	651	661	SHALE						
301	310	LIME	661	662	LIME			T.D. 1038'			
310	315	LIMEY SHALE	662	680	SHALE						
315	352	SANDY SHALE	663		GAS TEST 11# 1/2"						
352	420	SAND (WET DAMP)	680	687	BLACK SHALE						
377		WENT TO WATER	687	688	COAL						
420	450	SHALE	688	708	SHALE						
450	455	BLACK SHALE	708	709	COAL						
455	477	LIME (PAWNEE)	709	715	SHALE						
477	480	SHALE	713		GAS TEST 10# 1/2"						
480	488	BLACK SHALE	715	728	SAND						
487		GAS TEST 3# 1/8"	728	775	SHALE						
488	519	SHALE	775	782	BLACK SHALE						
519	547	LIME (OSWEGO)	782	790	SHALE						

RECEIVED
 KANSAS CORPORATION COMMISSION
 APR 13 2006
 CONSERVATION DIVISION
 MOBILE KS