


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CITIES SERVICE OIL CO.
Farm- Wilson No. 257

SEC. 8 T. 25 R. 5E
CS/2 S/2 SW
1320' N, 660' E of SW cor.

Total Depth. 2619'
Comm. 10-30-53 Comp. 11-15-53
Shot or Treated.
Contractor. White & Ellis Drlg. Co.
Issued. 4-24-54

County Butler
KANSAS



CASING:

10" 91' cem w/65 sx
7" 2568' cem w/175 sx

Elevation. 1377' RTB

Production. I.P. 269 oil, 0 wtr,
24 hr. NPO
(Arb. G.P. & Az.)

Figures Indicate Bottom of Formations.

dirt	4
lime	15
shale	25
lime	110
lime & shale streaks	320
shale & lime	435
sand	450
shale & shells	720
sand	745
shale & shells	830
lime	900
shale & shells	1160
lime	1375
shale & shells	1400
lime (sandy, oil)	1615
shale	1635
lime	1660
shale	1700
lime	1820
shale	1990
lime (K.C.)	2170
shale & lime	2381
lime & shale	2619
Total Depth	

2516 = 2516'
2568 = 2568'

Gun Perf. 2512 $\frac{1}{2}$ - 21 $\frac{1}{2}$ ' with 23 shots.
Gun Perf. 2452-58' with 21 shots.
Set Baker Packer 2438'. Squeeze formation 2452-58'
with 30 sx cem.
Gun Perf. 2530-31' with 16 holes.
Set Baker Retainer 2500'. Squeeze formation w/50
sx. 31 sx into formation.
Gun Perf. 2512-21' with 22 shots.
Gun Perf. 2452-58' with 1t shots.
Gun Perf. 2417-22' with 21 shots.
Set Lane Wells Bridge Plug 2440-44'
Gun Perf. 2403-13' with 24 shots.
Gun Perf. 2394-2413' with 23 shots.
Gun Perf. 2394-2403' with 21 shots.
Az. with 500 gals. Dowell XX. 85 bbls. load oil.
Tested & recovered load oil.

Set pumping unit.

All meas taken from RTB

Tops:
Lansing 1697
Base Lansing 1826
Kansas City 1981
Base Kansas City 2149
Arbuckle 2392

1710-14'	F.S.O.
1713-22'	S.O.
1796-1807'	S.S.O.
2008-11'	S.S.O.
2037-44'	F.S.O.
2392-95'	S.O.
2395-2429'	G.S.O.
2430-59'	G.S.O.
2459-80'	S.S.O.
2480-2514'	V.S.S.O.
2514-15'	G.S.O.
2517-25'	S.O.
2525-67'	V.S.S.O.
2577-80'	S.S.O.
2580-2619'	V.S.S.O.

Core #1 2382-2429'
Core #2 2430-80'
Core #3 2480-2515'
Core #4 2517-67'
Core #5 2569-2619'

Steel Line Measurement.

1623 = 1623'
2350 = 2350'
2382 = 2382'
2430 = 2430'
2480 = 2480'