

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company- CITIES SERVICE OIL COMPANY
Farm- Wilson No. 258

SEC. 8 T. 25 R. 5E

NE SE NW

990' N, 380' W of Center

Total Depth. 2151

Comm. 11-16-53

Comp. 11-20-53


Shot or Treated.

Contractor. White & Ellis Drlg. Co.

Issued. 6-19-54

County Butler

KANSAS



CASING:

8 5/8" 94' cem. w/64 sx

5 1/2" 2145' cem. w/150 sx

Elevation. 11402 R.T.B.

Production. 23 1/4 - 37- 16 hrs.
(K.C. Ls. G.P. & Az.)

All measurements taken from R.T.B. Figures indicate Bottom of Formations.

dirt	3	Perf. w/6 shots 2001-2008
lime & shale	25	Set Lane Wells Packer at 1999'
lime	40	Az. w/1500 gals. Chem. Process.
shale & shells	70	(46 bbls. load)
lime & shale	94	Tested & recovered load oil.
lime	140	Set packer at 1996'
redrock	150	Az. w/1500 gals. 2001-2008'
shale	170	(9 bbls. load)
lime	195	Tested & recovered load oil.
redrock	205	Set pumping unit.
lime	260	
shale	275	
redrock	285	
shale & shells	510	
sand oil	595	
sand	620	
shale	670	
sand oil	700	
shale & shells	810	
lime & shale	900	
shale & lime streaks	990	
shale & shells	1140	
lime	1280	
sand	1340	
shale & lime	1410	
sand	1550	
shale sandy	1605	
shale & shells	1700	
lime	1805	
shale	1975	
lime	2138	
shale	2151	
Total depth		

Tops:

Lansing	1699
Base Lansing	1828
Kansas City	1975
Base Kansas City	2138

Steel Line Measurement:

1603 = 1603

2151 = 2151

1724-34'	S.O.
1736-45'	S.O.
1759-51'	S.O.
1987-91'	F.S.O.
2001-07'	F.S.O.
2034-41'	S.S.O.
2063-70'	S.S.O.
2084-90'	S.S.O.
2105-07'	S.S.O.

Drill. In:

Drld. cem. to 2138

Perf w/21 shots 2001-2008'

Perf. w/24 shots 1986-1992'