


State Kansas County Pawnee
Company G. M. R. Oil Co Well No. 2
Farm Aldrich 2nd
Survey

Block No. Sec. 3 Twp. 23 Range 16^W

Co-Ord. Re Re Su Elev. 2053 K.B.
Rig #3



50% - Chicago Group
10% - Wm. Graham Oil Co.
40% - G. M. R. Oil Co.

NOTE: Show Sketch of Lease and Well Location in Above Space

330 Ft. from N. Line Ft. from S. Line
Ft. from W. Line 330 Ft. from E. Line

Date	Depth	
		4-12 MIRT Spudded 4-12
4-13-54		228' 8 5/8" w/16 5/8" Cenw. 2 gal. 4 c.c. Plugdown @ 12:45 this morn. NOC
4-14	1005	Anhydrite
	1178'	Dreg.
4-15	2019	✓
4-16	2330	✓
4-19	3402	✓
	3442'	✓
4-20	3609'	Draw Zone (-1556)

Date	Depth	Well #2 703488 3620' Lansing (-1562)
4-20	3615'	Drilling
4-21	DST #1 3612-3644	Open 1 hour, closed 20" Gas to surface in 12". Rec. 60' very sh. acrn. BNP 1170, I.F.P. 80, F.F.P. 80. DST #2 3647-3662 Open 1 hour, closed 20 min. ^{to be taken out} Gas to surface in 3 min. Oil to surface in 58 min. ^{Rec 3662 free oil} Flo to pits for 2 hrs. BNP 1120±
4-22	3770	Dreg.
4-23	3770	About ready to come out of the hole for dst. Started to test yesterday, had to recon- dition mud. If they don't get a dst this run, will drive ahead.
	DST 3746-70	Op 1 hr. cl. 30" Rec. 134' muddy water. BNP 1240 3850 B/K.C. (-1797)
4-24	3855	Drilling
4-26	4083'	Circ. for sample.
	3985	congl. (-1932)
	4062	Simpson (-2009)
	4081	AR Buckle (-2028)
4-27	4087	R.T.D. 5 1/2" @ 4084 w/125 P.O. 9:45 p.m. 4-26

State Kansas County Pawnee

Company GMR Oil Company Well No. 2


Farm Aldrich

Survey _____

Block No. _____ Sec. 3 Twp. 23S Range 16W

Co-Ord. _____ Elev. 2053 KB

NE NE SW



Page 2

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
5-7-54	MICT today. Cleaned out to 4056.	
	Ran Lane-Wells Log.	
5-10	Perf 3707-11 w/12 ^S . 3½ BOPH, 10% wtr.	
5-11	L-W Plug set @ 3690 to perf upper zone	
	Perf Lansing 3648-56 w/23 ^S .	
	Acidized w/2000 gals.	
	Swb & fl 73 BOPH - 3 hrs	
	" 16 " - 2 hrs	
	" 23.20 " - Next hr	

[illegible]