

State Kansas County Pawnee
Company G-M-R Oil Company Well No. 1 ✓
Farm Higgins "A"


Survey

Block No. Sec. 19 Twp. 22S Range 18 W

Co-Ord. Elev. 2110 K.B.

NE NE SW

Rig 1



1/2 - Chicago Group

1/2 - G-M-R Oil Co.

O.L.R.I. - Tommy Wright

\$4000. DHM - Gulf Oil Corp.

AM 2-8445

NOTE: Show Sketch of Lease and Well Location in Above Space

- 330 Ft. from N. Line Ft. from S. Line
Ft. from W. Line 330 Ft. from E. Line

Date	Depth	
		M.I.R.T. 7-29-54
7-30	555	255' 12-1/4" Hole
7-31		8 5/8" @ 255' W/175 Sx.cem.
		3 c.c., 2 gel. P.D. 2:30 pm
		7-30th. W.O.C.
8-2	2409	Drilling
8-3	2808'	Drilling
8-4	3227'	"
8-5	3600	"
8-6	3680 3765	Heelover (-1570) Brown Lime (-1655)

Date	Depth	703507
	3775	Lansing (-1665)
		Conditioning hole to dst
8-9	4229	Drilling
8-10	4346	"
	4296	Mississippi (-2186)
8-11	4457	Drilling
8-12	4400 ⁴³⁵⁰	Kinderhook <i>Sh</i> (-2250)
		D.S.T. 4406-61' Op. 60"., Cl. 20
	Rec. ^{15'} 20'	Mud. BHP 240#. <i>EEFF-0</i>
	4512	Drilling
8-13	4591	"
	4468	Viola (-2358)
	4592 ⁴⁶⁰²	Simpson (-2492)
	4648	Arbuckle (-2538)
8-14	4698	R.T.D. Sj
		D & A