

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

15-16-12W

Company - DEREY OIL
Farm - Kramer

No. 3

SEC. 15
NW NW NW

T. 16

R. 12W

Total Depth. 3322

Comm. 11-2-49

Shot or Treated.


Contractor.

Issued. 1-21-50

Comp. 11-14-49

County. Barton

KANSAS



Elevation. 1869 *Ind.*

Production. 57 BOPD

CASING:

8" 543' con. w/275 sx.
4 1/2" 3320

Figures Indicate Bottom of Formations.

shale	45
shale & shells	320
sand	360
shale & shells	410
lime & anhyd.	440
lime & shale	470
shale & shells	540
red rock	780
anhyd.	812
shale & shells	950
shale & shells & red rock	1330
shale & shells	1480
shale & lime	1905
lime	1955
lime & shale	2045
lime brkn	2135
lime & shale	2630
lime	3094
D.S.T.	
lime	3322
Total Depth	

Tops:

Heebner	2950
Lansing	3055
Arbuckle	3319

Completion:

Drilled com. & shoe. Clean out to 3321
to show. D.D. 3322. Hole filled 950'
in 9 hrs., no wtr. Swab test 2 1/4 BOPH,
treated w/200 gal. acid. Swab test 57
BOPD, no wtr. P.O.P.