

STOKES #55 33-25-5
Butler Co., Kansas.

Location
659' from N. line.
189' from E. line.

Sand record
615-620
640-655
2458-2500

Dril. comm. Apr. 16, 1917
" comp. May 24, 1917

Csg. record
12 $\frac{1}{2}$ 666'
8 $\frac{1}{2}$ 1774
6 5/8 2458' 6"
2 2467'
11/16 rods 2400'

Prod. 150 bbls. 1st 24 hrs.

Lime	light	med	60	60	
slate	light	med	15	75	
lime	light	med	10	85	
slate	grey	soft	40	125	
lime	light	hard	10	135	
slate	grey	soft	10	145	
rock	red	soft	5	150	
slate	dark	soft	35	185	
lime	dark	hard	5	190	
slate	dark	soft	35	225	
lime	light	hard	20	245	
slate	light	med	40	285	
rock	red	soft	10	295	
lime	white	hard	15	310	
slate	light	soft	50	360	
lime	light	med	15	375	
slate	dark	soft	25	400	
lime	light	med	10	410	
slate	dark	soft	15	425	
lime	white	hard	10	435	
slate	dark	soft	50	485	
lime	light	hard	15	500	
slate	dark	soft	10	510	
sand	dark	soft	10	520	2 bailers H2O
slate	dark	soft	95	615	
sand	dark	soft	5	620	oil
slate	dark	soft	20	640	H2O
sand	dark	soft	15	655	oil
slate	dark	soft	15	670	
lime	dark	hard	5	675	
slate	dark	soft	15	690	
lime	white	hard	10	700	
slate	white	soft	40	740	
lime	light	hard	10	750	
slate	light	med	50	800	
lime	white	hard	25	825	2 bailers H2O
slate	light	soft	75	900	
lime	white	hard	20	920	
sand	white	soft	20	940	
slate	white	soft	20	960	
lime	white	hard	10	970	
sand	grey	soft	30	1000	
lime	light	med	15	1015	
slate	grey	soft	45	1060	

STOKES #55 (cont)

lime	white	hard	5	1065	
slate	gray	soft	4	1069	
lime	white	hard	16	1085	
slate	dark	soft	25	1110	
sand	white	hard	5	1115	little gas
slate	dark	soft	35	1150	
lime	white	Med.	25	1175	little gas
slate	dark	soft	30	1205	
lime	light	Med.	25	1230	
slate &	shells	light med.	10	1240	
lime	white	hard	20	1260	
slate	dark	soft	13	1273	
lime	white	hard	27	1300	
lime	light	Med,	25	1325	
slate	dark	soft	50	1375	
lime	brown	hard	15	1390	
slate	black	soft	15	1405	
lime	dark	Med.	20	1425	
slate	dark	soft	35	1460	
lime	light	hard	12	1472	
slate	gray	soft	53	1525	
lime	light	Med.	20	1545	
slate	gray	soft	50	1595	
lime	light	Med.	5	1600	
slate	dark	soft	75	1675	
lime	white	hard	50	1725	water & oil
slate	light	soft	20	1745	
lime	white	hard	75	1820	little water
slate	dark	soft	30	1850	
lime	light	Med.	10	1860	
slate	gray	soft	90	1950	
lime	light	hard	25	1975	little oil
sand	light	soft	10	1985	1 barrel of water
lime	gritty light	Med.	15	2000	little oil
lime	white	hard	80	2080	
slate	gray	soft	20	2100	
lime	white	hard	10	2110	
slate	gray	soft	100	2210	
lime	white	hard	28	2238	
slate	gray	soft	7	2245	
lime	dark	hard	8	2253	
slate	gray	soft	42	2295	
lime	dark	hard	20	2315	
slate	dark	soft	115	2430	
slate	red	soft	8	2438	
slate	black	soft	20	2458	
sand	dark	soft	42	2500	oil
slate	gray	Med.	12	2512	
sand	light	hard	7	2529	
sand	dark	soft	3	2522	water

Plugged back to 2506'