

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

33-16-14

Company- E. K. CAREY DRILLING CO., INC.
Farm- Stein No. 7


SEC.

33 T. 16 R. 1W
NW SE NW

Total Depth. 2607
Comm. 8-11-53 Comp. 8-18-53
Shot or Treated.
Contractor. E. K. Carey
Issued. 11-7-53

County

Saline
KANSAS



CASING:

8 5/8" 127' cem. w/85 sx
5 1/2" 2599' cem. w/125 sx

Elevation. 1274' DF

Production. 146 BO & 12% wtr

Formations K.B.

Figures Indicate Bottom of Formations.

cellar	7
shale	15
sand	30
shale	60
lime & shale	127
lime	730
lime & shale	1630
lime	1750
lime & shale	1905
shale	1987
lime	2150
lime & shale	2260
lime	2360
shale & lime	2535
shale	2597
chat	2600 RTD
chat	2607
Total Depth	

TOPS:

Lansing 1987
Mississippi Chat 2597 1/2

D.S.T. 1993-2010' w/17' anchor.
Tool open 1 hr. 15 min.,
rec. 35' heavy oil cut
mud. 10 m. BHP 100#, FFP
30#. Slight blow through
out test.