

API: 15-205-24, 247

WELL RECORD

2-28-15E

Well No. 9	Farm	Brazil II	Producer	Eagle Resources Inc.
Location	SW $\frac{1}{4}$ SE $\frac{1}{4}$	Sec. 2	Twp. 28	Rg. 15
Elevation		State	Kansas	County
Kind (Oil, Gas, Water, Dry Hole)		Contractor	Fleming Drilling, Inc.	
Producing formation		Top		Bottom
Shot with	qts.	from		to
Packer Set at		Kind		Size
Liner	from	to	Perforated from	to

LOG

Thick- ness	Strata	Depth	Thick- ness	Strata	Depth
3	top soil and lime	3	6	sand, shaley/odor	
17	lime, surface	20			860
2	lime	22	50	sand, shaley	910
103	shale	125	12	shale	922
26	lime	151	18	shale	940
50	shale	201	2	shale, sandy	942
14	lime	215	2	sand, oil show	944
35	lime, show	250			
91	shale	341	2	oil sand, lam.	946
61	lime	402	1	sand, lam	947
22	lime	424	7	shale	954
20	shale	444	3	sand lam. show of oil	
2	lime	446			957
24	shale	470	6	shale	963
20	lime, brkn.	490		drilled:	
26	lime, gas odor	516	42	shale	1005
33	lime	549	3	sand, gas odor	1008
85	shale	634	9	blk. shale	1017
24	lime, brkn.	658	1	coal	1018
88	shale	746	2	whit. shale & sand	
2	lime	748			1020
5	shale	753	9	drk. & whit. sand/odor	
20	lime	773			1029
30	shale	803	6	gray shale, sandy	1035
17	lime, 20'	820	7	shale	1042
6	shale	826	38	shale	1080
5	lime, 5'	831	5	shale, sandy odor	1085
16	shale	847	2	oil sand, shaley	1087
1	lime	848			
6	shale sandy	854	2	oil sand	1089
			4	shale	1093

Total Depth	1150'
Open Hole Set 20' of pipe for surface	
Cemented with 4 sacks cement.	
Casing	at
Casing	at
Casing	at
Cement Ran 1140' of 2 7/8" pipe. Cent#	
and 2nd ft above S.N. . Floatshoe on	
Tubingbottom. S.N. 1082'	
Rods	
Additional Information	
Started 7/16/85	
Completed 7/27/85	
1 oil sand 1094	
1 shale 1095	
2 oil sand 1097	
1 shale streaks oil sand 1098	
2 oil sand 1106	
1 shale 1107	
drilled:	
1 shale 1108	
4 sand, shaley show of oil 1112	
12 sand, shaley, odor 1126	
10 sand, shaley show of oil 1142'	
8 sand, shale/odor 1150	

Date Completed

O. K.

Superintendent