

WELL COMPLETION REPORT AND DRILLER'S LOG

State Geological Survey
KANSAS
WICHITA BRANCH

S. 3 T. 28S R. 15 E
Loc. 200'WL & 1140'SL

API No. 15 — 205 — 21,050
County Number

County Wilson

Operator
L & L Oil Co.

Address
P. O. Box 13 Benedict, Kansas 66714


Well No. #1-A Lease Name Parker

Footage Location
1140 feet from (N) (S) line 200 feet from (E) (W) line

Principal Contractor Company Tools Geologist

Spud Date July 10, 1980 Date Completed July 25, 1980 Total Depth 1065 P.B.T.D.

Directional Deviation Oil and/or Gas Purchaser
Square Deal Oil Co., Inc.



Locate well correctly
Elev.: Gr. _____
DF _____ KB _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	9 5/8"	7"		52'	Portland A	18	
Production	5 1/8"	3 1/2"		1055'	Portland A	128	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			3		1012-1036
Size <u>1"</u>	Setting depth <u>1020</u>	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
100 sacks of sand, 180 bbl of water	1012-1036

INITIAL PRODUCTION

Date of first production <u>May 1, 1981</u>	Producing method (flowing, pumping, gas lift, etc.) <u>Pumping.</u>
RATE OF PRODUCTION PER 24 HOURS <u>0</u> bbls.	Gas <u>40</u> MCF Water <u>40</u> bbls.
Disposition of gas (vented, used on lease or sold)	Gas-oil ratio CFPB
	Producing interval(s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator _____ DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.: Oil

Well No. #1-A Lease Name Parker

S 3 T 28 SR 15 ^E_W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Soil	0	10		
Clay & Shale	10	45		
Shale	45	77		
Lime	77	85		
Shale w/lime streaks	85	109		
Shale	109	139		
Lime-White	139	169		
Brown Lime	169	193		
Sand Gray	193	197		
Sand & Black Shale	197	203		
Shale w/Lime Streaks	203	250		
Shale/w Coal	250	262		
Brown Lime	262	272		
Shale W/Lime	272	281		
Shale	281	290		
Lime	290	324		
Lime & Shale	324	337		
Lime	337	370		
Shale & Coal	370	373		
Lime, Shale, Coal	373	375		
Shale, Coal	375	380		
Gray Shale	380	388		
Gray Shale	388	399		
Lime Shale	399	405		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Douglas L. Leach

Signature

PARTNER

Title

12-1-81

Date