

11-28-15E

Company

(KGS-DRL)

Sec. 11 T. 28 R. 15

Farm *Bird Well.*

No. 3

Loc.

County Wilson

Total Depth 1117'


Comm. 11-8-1949

Comp. 11-18-1949

Shot or Treated

Contractor

Issued



Casing

20 in. 10 in. 10' pulled

15 1/2 8 1/4

12 1/2 6 5/8

13 3/8 5 3/16

8" 54 5'

6" 920'

Figures Indicate Bottom of Formation

Elevation

Production

soil & clay	4	lime	727
lime	20	shale	738
shale	132'	lime	741
lime	147	shale	743
lime & shale	162	lime	768
shale	236	shale D.	783
lime	238	shale L.	797
shale D.	255	lime	814
lime	264	shale, water	818
shale D.	292	lime	824
shale W.	310	shale B. water	837
lime	320	lime	841
shale	338	shale	912
lime	342	lime	914
shale	348	shale B.	917
lime	356	shale L.	923
lime sandy	421	lime	924
shale, water	424	shale D.	950
lime	453	sand, S.O.	955
shale D.	468	shale	1073
lime	492	sand, S.O.	1111
shale	494	sand, no oil	1117
lime	514		
S.O. 513 to 516			
shale	592		
lime	597		
shale	607		
lime	610		
shale	620		
lime	622		
shale	624		
lime	637		
shale	726		

Log was drilled for C.R. Miller & Clifton Paxson of California Drillers: R.L. Wyckoff of Independence, Ks. Shot with 60 qts. Nitro jeletine from 1080' to 1110', by Frank Herbert of Independence, Ks. on 11-22-1949. Oil before shot was about 2 gallons in 24 hours. Oil after shot was about 30 gallons in 24 hours. This well was personally supervised & logged by R.L. Wyckoff.