

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

28-16-12W


Company- HARMS-BURT DRILLING CO.
Farm- Hitschman No. 1

SEC. 28 T. 16 R. 12W
SE NW SE

Total Depth. 3400'
Comm. 8-25-55
Shot or Treated.
Contractor.
Issued. 3-17-56

Comp. 9-2-55

County Barton
KANSAS



CASING:
8 5/8" 210' cem w/125 sx

Elevation. 1906' RB

Production. Dry

Figures Indicate Bottom of Formations.

soil & clay	20
lime	40
shale	210
shale & shells	350
sand	420
shale & shells	500
red bed	630
red bed & shale	810
anhydrite	835
shale & shells	1140
lime & shale	1535
lime	1630
lime & shale	2130
lime	2185
lime & shale	2225
shale & lime	2550
lime & shale	2750
lime	2785
lime & shale	2895
lime	3033
lime & shale	3098
lime	3385
Arbuckle lime	3400
Total Depth	

Tops:	
Anhydrite	810
Heebner	3010
Brown Lime	3098
Lansing-Kansas City	3114
Arbuckle	3385

DRILL STEM TESTS:

#1 3277-3315', open 30 min., shut in 20 min.
Rec. 3 feet of mud. IFP Off, FFP Off, BHP 90#.