

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,

Wichita, Kansas

28-16-12W

Company- DUKE DRILLING CO.
Farm- Laudick No. 2

SEC. 28 T. 16 R. 12W
SW NE NW

Total Depth. 3378'

Comm. 1-16-58


Comp. 1-26-58

Shot or Treated.

Contractor. Duke Drlg.

Issued. 4-26-58

County Barton
KANSAS



Elevation. 1918' KB

Production. 25 BOPD

CASING:

8 5/8" 325'
5 1/2" 3370'

Figures Indicate Bottom of Formations.

surface clay & sand	70
shale	85
sand	100
shale	140
sand	190
shale & sand streak	250
sand	275
shale	400
sand	410
shale	420
sand	425
shale	465
sand	470
shale	493
very hard sand	496
shale	550
red bed	806
Anhydrite	841
shell & shale	1215
salt & shale	1480
shale & shell	1515
lime & shale	1830
sand	1838
lime & shale	1868
sharp sand	1878
lime & shale	2631
lime	2740
lime & shale	2890
lime	3007
Heebner	3100
lime	3113
Lansing	3290
lime	3364
Arbuckle	3378 RTD
Total Depth	

TOPS:

Anhydrite	806
Heebner	3007
Toronto	3023
Douglas	3036
Lansing	3113
Conglomerate	3350
Arbuckle	3364