

SUTCLIFFE PIPE & SU PLY

SUTCLIFFE

ORIGINAL

PHONE HE 1-1940 CHANUTE
PHONE TEMple 8-3601 WICHITA

Well Record

119 S. GRANT, CHANUTE, KANSAS
6705 N. BROADWAY, WICHITA, KANSAS

COMPLETE LINE OF NEW & USED PIPE - BELTING - STORAGE TANKS - WIRE LINES

Well No. 1-B Farm Roberts Producer Jones Oil Company
 Location NW¹ NW⁴ Sec. 11 Twp. 28 Rg. 15E
 Elevation _____ State Kansas County Wilson
 Kind (Oil, Gas, Water, Dry Hole) _____ Contractor Sutcliffe Pipe & Supply
 Producing formation _____ Top _____ Bottom _____
 Shot with _____ qts. _____ from _____ to _____
 Packer set at _____ Kind _____ Size _____
 Liner _____ from _____ to _____ Perforated from _____ to _____

LOG

Thickness	Strata	Depth	Thickness	Strata	Depth
2	Soil	2	13	Shale & sandy sh	920
17	Lime	19	13	Gray sandy shale	
103	Shale	122		to dark	933
20	Lime	142	3	Black shale	936
60	Shale	202	4	Lite sdy. sh.	940
42	Lime	244		Core # 1	
58	Shale	302	4	Broken sand	944
33	Lime & shale brk	335	2	Sand	946
83	Lime	418	1	Coal	947
27	Sand & sandy shale	445	5	Shale	952
				Drilled	
10	Lime	455	13	Shale -lite to	
10	Shale	465		dark	965
74	Lime	539	9	Shale	974
53	Shale	592		Core # 2	
21	Lime w/shale brk	613	5	Shale	979
12	Shale	625			
15	Lime	640			
93	Shale -sand & sandy shale	733			
34	Lime	767			
23	Shale	790			
17	Lime	807			
5	Shale	812			
7	Lime	819			
13	Sandy shale-gassey	832			
13	Sandy shale S.D.	845			
60	Dark sandy shale				
	& shale	905			
2	Lime	907			

Total Depth 979'
 Open Hole _____
 Casing 7" at 65'10"
 Casing _____ at _____
 Casing _____ at _____
 Cement _____
 Tubing _____
 Rods _____
 Additional Information
Run 400' - mixed 5 sacks cement & spotted at 400' - pulled up to 140' & spotted 5 sacks cement - pulled out & put 2 sacks at surface -
 Plugged:
Heavy mud in bottom from 979' to 800'
Cement plug from 400' to 370'
Another cement plug spotted from 140' to 110'
All cement run funnel methos thru drill pipe
60' of 7" S.P. left in hole cemented in 1 sack of dry cement in top of S.P.

Date Completed February 26, 1962

O. K.

Superintendent

Started February 19, 1962