

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOGState Geological Survey
WICHITA BRANCHAPI No. 15 — 205 — 20,706
County NumberS. 13 T. 28 R. 15 E
Loc. 480¹ FSL & 150' FWL
County Wilson

Operator

L & L Oil Co.

Address

P. O. Box 13 Benedict, Kansas 66714

Well No.

#3A

Lease Name

Morton

Footage Location

480

feet from (S) line

150

feet from (W) line

Principal Contractor

L. & L. Oil Co. Tools

Geologist

Spud Date

12 10 79

Date Completed

12 22 79

Total Depth


1085

P.B.T.D.

Directional Deviation

Oil and/or Gas Purchaser

Square Deal Oil Co., Inc.



Locate well correctly

Elev.: Gr.

DF

KB

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	9"	7"	17#		A	20	
Production	5 1/4"	2 1/2"	6.50	1081'	A	105	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			3	2/1/8	1008 to 1022
TUBING RECORD					
Size	Setting depth	Packer set at			
1"	1065				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Fracture 50 Sx. W/ 180 BBL. Water	1008 to 1022

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
21-18-80		Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil 30	Gas bbls.	Water MCF	5	Gas-oil ratio bbls.
Disposition of gas (vented, used on lease or sold)			Producing interval (s) 24 Hours		
			CFPB		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator L.&L. Oil Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No. 3A	Lease Name Morton	Oil	
S <u>13</u> T <u>28</u> R <u>15</u> E <u>XX</u>			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	
Soil	0	6	
Clay	7	14	
Shale	15	94	
Lime	95	112	
Shale W/Lime	113	126	
Shale	127	195	
Lime	196	205	
Shale	206	277	
Lime	278	282	
Shale	283	303	
Lime	304	320	
Shale W/ Lime	321	504	
Lime	505	520	
Shale	521	567	
Lime	568	570	
Shale	571	589	
Shale W/Lime	590	1002	
Gas Sand	1003	1007	
Oil Sand	1008	1022	
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 Signature Partner Title 3-1-80 Date		