

KANSAS

IMPORTANT
Kans. Geo. Survey request
samples on this well.

WELL COMPLETION REPORT AND
DRILLER'S LOG

State Geological Survey
WICHITA BRANCH

API No. 15 — 205 — 20,949
County Number

S. 13 T. 28 R. 15 E
Loc. 1800' SL & 450' WL
County Wilson

Operator

L & L Oil Co.

Address

P. O. Box 13 Benedict, Kansas 66714

Well No.

#7A

Lease Name

Morton

Footage Location

1800 feet from (N) (S) line 450 feet from (E) (W) line

Principal Contractor

Company tools

Geologist

Spud Date

5-15-80

Date Completed

5-20-80

Total Depth


1075

P.B.T.D.

Directional Deviation

Oil and/or Gas Purchaser

Square Deal Oil Co.



Locate well correctly

Elev.: Gr. _____

DF _____ KB _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	9-5/8	7"	20	53	Portland A	25	
Production	5-1/4	2-7/8	6.5	1065	Portland A	130	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			3	2-1/8	1037-1052
TUBING RECORD					
Size	Setting depth	Packer set at			
1"	1050				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
50 sacks sand, 200 bbl. gelled water	1037-1052

INITIAL PRODUCTION

Date of first production

5-25-80

Producing method (flowing, pumping, gas lift, etc.)

Pumping

RATE OF PRODUCTION
PER 24 HOURS

Oil

15

Gas

bbls.

MCF

Water

none

Gas-oil ratio


bbls.

CFPB

Disposition of gas (vented, used on lease or sold)

Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator L & L Oil Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: oil	
Well No. 7A	Lease Name Morton		
S <u>13</u> T <u>28</u> R <u>15</u> ^E			
WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
Lime Oil Sand Shale	825 1032 1054	845 1054 1075	
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 Signature Partner Title 6-1-80 Date		