

State Geological Survey KANSAS WICHITA BRANCH

WELL COMPLETION REPORT AND DRILLER'S LOG

API No. 15 — 205 — 20,708
County Number

Operator

L & L Oil Co.

Address

P. O. Box 13 Benedict, Kansas 66714

Well No.

#6A

Lease Name

Morton

Footage Location

810

feet from (N) (S) line

450

feet from (E) (W) line

Principal Contractor

L & L Oil Co.

Geologist

Spud Date /

11-18-79

Date Completed

1-3-80

Total Depth

1078

P.B.T.D.

Directional Deviation


Oil and/or Gas Purchaser

Square Deal Oil Co., Inc.

S. 13 T. 28 R. 15 E
Loc. 810 FSL & 450 FWL

County Wilson

640 Acres
N



Locate well correctly

Elev.: Gr. _____

DF _____ KB _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	8-7/8	6-5/8	#17		AA	33	
Production	5 1/4	2 7/8	6.50	1078	A	155	2% gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	2-1/8	1032-1048
TUBING RECORD					
Size	Setting depth	Packer set at			
1"	1068				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
100 Sx sand, 240 BBL. Water	1032 to 1048

INITIAL PRODUCTION

Date of first production 4-7-80		Producing method (flowing, pumping, gas lift, etc.) Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil 20 BBL. bbls.	Gas MCF	Water 5 bbls.	Gas-oil ratio CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator
L&L Oil Company

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No.

6 A

Lease Name

Morton

Oil

S 13 T 28 R 15 E

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

Soil

0

2

Clay & Rock

3

14

Shale

15

90

Lime

90

102

Lime W/ Shale

103

125

Shale

126

193

Lime

194

205

Shale

206

275

Lime

276

280

Shale

281

300

Lime

301

320

Shale W/ Lime

321

504

Lime

505

522

Shale

523

569

Lime

569

570

Shale

571

584

Shale W/ Lime

585

1028

Gas Sand

1029

1032

Oil Sand

1033

1050

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Douglas L. Lamb

Signature

Partner

Title

5-1-80

Date