


KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOGState Geological Survey
WICHITA BRANCHAPI No. 15 — 205 — 20951
County NumberS. 13 T. 28 R. 15 E
2460' FSL; 150' FUL
Loc. _____

County Wilson

640 Acres
N

Locate well correctly

Elev.: Gr. _____

DF. _____ KB. _____

Operator
L & L Oil CompanyAddress
P.O. Box 13 Benedict, KS 66714

Well No. 9 A Lease Name Morton

Footage Location
2460 feet from (S) line 150 feet from (W) linePrincipal Contractor
Company tools

Geologist

Spud Date 5-30-80 Date Completed 6-4-80 Total Depth 1080 P.B.T.D.

Directional Deviation Oil and/or Gas Purchaser
Square Deal Oil Co.

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	9 5/8"	7"	20#	54'	Portland A	20	
Production	5 1/8"	2 7/8"	6.5	1076'	Portland A	77	2 % Gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	2 1/8"	1012-1031
Size	Setting depth	Packer set at			
1"	1040'				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
200 bbl. gelled salt water, 75 sacks sand	1012-1031

Intent 5-14-1980 (KCC-1) INITIAL PRODUCTION

Date of first production 6-16-80 Producing method (flowing, pumping, gas lift, etc.)
pumping

RATE OF PRODUCTION PER 24 HOURS	Oil 5 bbls.	Gas MCF	Water 10 bbls.	Gas-oil ratio	CFPB
------------------------------------	-------------	---------	----------------	---------------	------

Disposition of gas (vented, used on lease or sold)

Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator L & L Oil Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Oil	
Well No. 9 A	Lease Name Morton		
S 13 T 28 R 15 E			
WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
			DEPTH
Lime	805	824	
Oil Sand	984	992	Cattleman
Oil Sand	1010	1032	Bartlesville
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	Douglas L. Land Signature Partner Title July 1, 1980 Date		