

WELL COMPLETION REPORT AND DRILLER'S LOG

KANSAS
State Geological Survey
WICHITA BRANCH


API No. 15 — 205 — 21,679
County Number

JS. 13 T.28 R. 15 E

Loc. 150' SL; 150' WL

County Wilson

640 Acres
N



Locate well correctly

Elev.: Gr.

DF KB

Operator L & L Oil Company			
Address Box 13, Benedict, Kansas 66714			
Well No. 15 A	Lease Name Morton		
Footage Location 150 feet from (T) (S) line 150 feet from (E) (W) line			
Principal Contractor Company Tools		Geologist	
Spud Date April 23, 1981	Date Completed May 4, 1981	Total Depth 1085	P.B.T.D.
Directional Deviation		Oil and/or Gas Purchaser Square Deal	

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	8 5/8"	7"		27'	Portland A	20	
Production	6 1/4"	2 7/8"		1078	Portland A	104	2% Gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	2 1/8" Alum	994 - 998
			2	2 1/8" Alum	1022 - 1026
			1	2 1/8" Alum	1032 - 1050

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
200 bbl gelled salt water, 50 sacks of sand	994 - 998
	1022 - 1026
	1032 - 1050

INITIAL PRODUCTION

Date of first production May 28, 1981		Producing method (flowing, pumping, gas lift, etc.) Pumping	
RATE OF PRODUCTION PER 24 HOURS	Oil 1 bbls.	Gas MCF	Water 15 bbls.
Disposition of gas (vented, used on lease or sold)		Producing interval (s)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator L & L Oil Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Oil
Well No. 15A	Lease Name Morton	
S. 13 T. 28 R. 15E		

WELL LOG			SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Lime	765	785		
Sand - Oil Show	992	1000		
Oil Sand	1020	1026		
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				

Date Received	<i>Donald R. Lamb</i>	
	Signature	
	Partner	
	Title	
	June 1, 1981	
	Date	