

Total Depth, 1990' PB 1987'


Comm. 10-6-57

Comp. 10-14-57

Shot or Treated.

Contractor. Shira Drlg. Co.

Issued. 10-18-58



CASING:

8 5/8" 297' w/200 sx cem.
5 1/2" 1989' w/70 sx cem.

Elevation. 1318' DE

Production. 26 BOPD

Figures Indicate Bottom of Formations.

(All Meas. fr RB 1' above DF)

(Sample data begin @ 837')

shale, wh lime	260
shale	300
lime, shale	837
lime, shale gry	1074
lime	1118
lime, shale	1150
lime	1170
lime, shale	1200
lime	1215
lime, shale	1314
lime	1355
shale	1374
lime	1390
shale	1410
lime	1420
shale	1447
lime	1457
lime, shale	1488
lime	1530
lime, shale	1578
lime	1610
lime, shale	1650
lime	1790
lime, shale	1890
shale, varigated	1928
sand, cherty, good odor, some stain & fluorescence free oil in mud & shale, barigated.	1964
lime, cherty	1990
Total Depth	
PB	1987

TOPS:

Tarkio	837
Howard	1074
Topeka	1118
Oread	1314
Heebner	1355
Brown Lime	1447
Lansing	1457
Kansas City	1578
Mississippian	1928
Mississippi Lime	1964

Ran Schlumberger Log.

Perf; 10-16-57 5 1/2" 1930-1962' w/128 shots.

Shot or Acid Record;

10-17-57 fr 1930-1962' Acid Frac:

6,000 G & 6,000# sand

2-14-58 fr 1930-1962' Acid-Petrofrac:

6,000 G & 6,000# sand.