

1-16-13W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PETROLEUM, INCORPORATED
Farm- Rude No. 1

SEC. 1 T. 16 R. 13W
NE SW NE

Total Depth. 3333'
Comm. 11-19-57 Comp. 11-29-57
Shot or Treated.
Contractor. Garvey Drilling Company
Issued. 3-15-58

County Barton
KANSAS



Elevation. 1898' DF

Production. 190 BOPD

CASING:

8 5/8" 430' cem w/225 sx
4 1/2" 3330' cem w/150 sx

Figures indicate Bottom of Formations.

surface soil & postrock	60
shale & shells	830
Anhydrite	860
shale & shells	1835
shale & lime	2120
shale & shells	2610
shale & lime	2755
lime	2915
lime & shale	3075
lime	3268
lime & shale	3320
lime	3323
Quartzite	3333
Total Depth	

TOPS: SCOUT	
Anhydrite	830
Heebner	2974
Toronto	2990
Douglas	3009
Brown Lime	3061
Lansing	3071
Quartzite	3312