


Total Depth. 2770'
 Comm. 8-19-58 Comp. 9-1-58
 Shot or Treated.
 Contractor. Lewis Drlg. Co.
 Issued. 10-25-58

County Clay
 KANSAS



Elevation. 1296' KB

Production. DRY

Figures Indicate Bottom of Formations.

surface, sand	40
lime	275
shale, lime	895
shale, lime stks	1065
Topeka lime	1155
lime, shale	1430
Kansas City lime	1545
lime	1725
lime, shale	1935
lime	1936
shale, lime	1940
Mississippi lime	1955
lime	2015
shale, lime	2187
lime	2550
Dolomite lime	2605
Viola lime, brown & cherty	2650
lime	2710
lime, shale, Simpson	2770
Total Depth	

TOPS: GEOL.

Topeka	1075
Heebner	1312
Lansing	1408
B/Kansas City	1745
Sand	1928
Mississippi chert	1940
Kinderhook	2011
Hunton	2183
Maquoketa	2514
Viola	2578
Simpson	2734
Simpson Sand	2752

DST #1 1929-1935 Opek 1 hr-
 weak blow thoroughout-rec. 15'
 muddy wtr & 1 gal oil. 20 min.
 ISIP showed 765# 20 min. FSIP
 failed IFP - zero; FFP - 75#.

DST #2 1941-1955 Open 1 hr-
 fair to good blow. Rec. 20' wtr.
 mud, specks of oil, and 240'
 muddy wtr. 20 mins. ISIP showed
 765# bottom hole, 20 min. FSIP
 showed 750# bottom hole. IFP 1f 5#
 and FFP of 105#.