


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - BIRD-HANLEY-SHEEDY
 Farm - Enloe No. 6.

SEC. 28 T. 25 R. 14 E
 NE SE SE

Total Depth. 1530'
 Comm. 6-1-43 Comp. 7-9-43
 Shot or Treated.
 Contractor. Flory
 Issued. 2-5-44

County. Woodson
 KANSAS



CASING:
 10" 650'
 8" 1063'
 65/8" 1446'

Elevation. _____

Production. Est. 150 B.

Figures Indicate Bottom of Formations.

soil	2
clay	8
lime	12
shale	65
sand (1BWPH 70-77)	90
shale	135
sand (1BWPH 145-60)	160
shale	183
lime	188
shale	193
lime (1BWPH 195-200)	198
shale	365
lime	560
shale	565
lime	645
shale	695
lime	697
shale	700
lime (2BWPH 710)	857
shale	1002
lime	1010
shale	1035
lime	1048
sand sh gas	1051
sd lime	1063
shale	1115
lime	1150
shale	1167
lime	1172
shale	1177
lime	1195
shale	1220
lime	1225
shale	1405
shale dk	1444
shale sdy	1446
slate lt	1447
shale dk	1448
slate dk	1449
shale sdy dk	1456
sand sh oil	1474
shale	1477
sand & shale	1492
shale dk	1530

Total Depth