

State Kansas County Barber

Company G-M-R Drilling Co. Well No. 1

Farm Donovan "F"

Survey

Block No. Sec. 9 Twp. 34S Range 13W

Co-Ord. C.P. 3500-50 S.P. 3650 Elev. 1729 KB

NE NE SE

Rig #2 1718 GL

3/8-G-M-R Drilling Co.

5/8-Chicago Group

Farmout from Sohio
DHM-GMR-M and Newmont
5500' test - Arbuckle

Geol: G. Klein to 4500. V. Hess to T.D.

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line 2310 Ft. from S. Line

Ft. from W. Line 330 Ft. from E. Line

Date	Depth	
		SPD 9-7-55
9-6		Start MIRT today.
9-7		MIRT
9-8	900	Running surface (Will run 320)
9-9		8 5/8" @ 320' w/225 sx cem, 2% gel, 5 c.c. PD 11 am 9-8
	1015	Drlg
9-10	2192	Drlg (Straight hole)
9-12	3510	Drlg (Mudded up this a.m.)
9-13		No Elgin Sd. Expect Douglas app 4000'.

Date	Depth	
		705601
	3945	On bottom w/new bit(1° @ 3945)
9-14	4028	Douglas Sd (-2299)
		DST #1 4021-55, op 1½ hr, cl 20". Gd bl throughout. Rec 80' drlg mud. IFP & FFP-70#. BHP-160#.
	4121	Drlg
9-15	4193	Brn Lime (-2464)
	4198	Lansing (-2469)
	4355	Drlg (½° off 4293)
9-16	4488	Drlg (1° off 4488)
9-17	4615	Drlg
9-19	4740	Marmaton (-3011) (Sli. show & some fracturing.)
		DST #2 4745-75', op 1 hr, cl 20". Wk bl 12". Rec 15' mud. IFP & FFP-50 BHP-60#.
		Log 4798
	4781	Miss (Cowley) (-3052) (-3069)
	4815	Circ for samples.
9-20		4822-52 Cherty dolo, stn, no free oil.
	4916	Drlg.
9-21	5027	Lost circulation (Regained about 4 p.m.)
9-22	5146	Viola (-3417)
	5155	Drlg.

