


Company - BRINEGAR BROWNLEE ALCOCK
Farm Fuhlhage No. 1

SEC. 27 T. 25 14E
NWC NE/4 SW/4
420' east 220' S

Total Depth 1490
Comm. 11-25-49 Comp. 12-6-49
Shot or Treated. shot 50 qts nit
Contractor.
issued. 2-4-50

County. Woodson
KANSAS



Copy

CASING:

10" 169' pulled
8 5/8" 786'9" pulled
6 5/8" #17 1429'8"

Elevation. _____

Production. 64 bbls per hr
(natural)

Figures Indicate Bottom of Formations.

soil and gumbo	10
lime	22
shale light	58
shale sdy	110
sand fr wtr	147
shale light	185
2 B.W.	
lime	189
shale	194
lime	197
shale	372
lime Topeka	420
shale	425
lime top K.C.	565
lime shells and shale	587
lime	645
H.F.W. 605	
shale light	675
lime	678
shale	700
lime	775
shale	778
lime stl line R	781
shale dark	787
lime	850
shale	996
lime	1001
shale	1010
lime	1014
shale	1020
lime	1023
shale	1034
lime	1046
shale	1117
lime	1140
shale	1145
lime	1149
shale	1152
lime	1165
shale	1172
lime	1177
shale and lime	1187
shale dark	1202
shale	1224
sand showing of oil	1244
shale	1280
lime	1283
shale sdy	1357
shale dark	1415
shale some grit	1425
shale light casing pt	1429
(steel line) o.k.	
<u>Drilling in under casing</u>	
sandy shale smelling oil	1435
shale light to drk	1440
shale some sand	1445

shale some sand	1450
more sand in shale lighter	1455
more sand in shale same	1460
sand- oil showing	1465
all sand- free oil	1470
sand light hole filling up	1475
sand the same extra good	1480-
500' oil in hole	
sand same but some finer	1485
Hole filling up	
sand similar to 1st screw	1490
1000' oil in hole- 3 hrs.	
some wtr showing in last screw.	
Total Depth	1490

2" tubing 1415'3
3-1 packer- Hensroth seat 4'4
3" anchor preferred 58'5

Shot record-- 50 qts nit from 1462
to 1478'

Six sacks Cal-Seal 30' from 1426 to 1456
on bridge

Top oil sand 1461' to 1490'
Showing wtr at 1490'
Bridge back to 1478'
flowing through packer at 11 bbls per hr.

Oil tests 39. corrected

Run 2" tubing with packer

12-27-49 Flowing through oil line to
batter 1000' away.