

State Kansas County Barton

Company G-M-R Oil Co. Well No. 1 C

Farm O. Maneth

Survey \_\_\_\_\_

Block No. \_\_\_\_\_ Sec. 32 Twp. 17S Range 14W

Co-Ord. \_\_\_\_\_ Elev. 1947 D.F.

1950 R.B.

SE SE SE


20% - a.a. Selligson  
 10% - a.a. Selligson Jr.  
 10% - Berta Selligson  
 10% - Wm. Binkham  
 12.5% - Dale Carnegie  
 27.5% - G.M.R. Oil Co.

*Lohmann-Johnson-Contd*

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line \_\_\_\_\_ Ft. from S. Line \_\_\_\_\_

Ft. from W. Line \_\_\_\_\_ Ft. from E. Line \_\_\_\_\_

Date	Depth	
		MIRT 1-8-51
		Spd. 1-9-51, 8 5/8" @ 945'
	931	Anhydrite - plus 1019
	945	Drlg.
1-13	2425	Drlg.
1-14	2825	Drlg.
1-15	3084	Drlg.
	3125	Heebner (-1175)
	3190	Lansing (-1240)
	3194-3202, 3215-22	ool. good por & Sat.

odor

Date	Depth	
		705795
Act #1	3192-3222	D.S.T. open 45 min. rec. 195' SW
1-17	3340	Drlg.
1-17	3421	Conglmoerate (-1471)
1-17	<del>3451</del> 3447	Arbuckle (-1497) (-1501)
Act #2	3451-54	D.S.T. open 20 min. rec. 155' Oil plus 30' water BHP 810#
	3454 R.T.D.	5 1/2" @ 3452 corr. fill 1100 ft. oil in 12 hrs.
2-2		D.P. - Swb. 6 BOPH <del>xxx</del> for 3 hrs.
	3451 - 3447	S.L.C.
		POP
	<del>3454</del>	R.T.D. <sup>1 1/2" @ 3452</sup> - pump 1 1/2 BOPH
2-15		State Phy. Pot. 55 BO, NW
2-20		Pump 25 BO <del>xxx</del> 9 hrs.
		500 acid - pump 1 BOPH
3-27-51	500 Acid	Down Annular space. Rods + string in hole
5-3-51	500 Acid	3300' 3 1/2" @ 3300' 3 1/2" @ 3300' 3 1/2" @ 3300'
5-4-51	500 Acid	3300' 3 1/2" @ 3300' 3 1/2" @ 3300' 3 1/2" @ 3300'
	3276-8/51	3. 420 WPH. D & A May 1951