

V W & B DRILLING CO.  
Box 7 N. Hwy. 169  
CHERRYVALE, KS 67335

Devlin Farm Well # 49

Sec. 3 T31S R21E  
Loc. NE of SW

Began Drilling 3-4-80 Completed 3-6-80

Drilled for Hickory Creek Oil Company

Figures indicate the bottom  
of the formation

1	Top Soil	1	11 Med. Shale	157
9	Gray Clay	10	1 Lime	158
6	Yellow Clay	16	6 Med. Shale	164
1	River Gravel	17	10 Lt. Shale	174
14	Lime	31	8 Med. Shale	182
1	Med. Shale	32	Start Core 182	
5	Blk. Shale	37	Stop Core 270	
1	Lt. Shale	38	7 1/2 Bartlesville Sand	256
13	Lime	51	9 Lt. Shale	265
5	Blk. Shale	56	1 Coal	266
5	Lt. Shale	61	7 Med. Shale	273
2	Lime	63	9 Lt. Shale	282
8	Sand (Gas)	71	8 Med. Shale	290
89	Med. Shale	140	11 Lt. Shale	301
6	Dk. Shale	146		

21 feet of 7 inch casing set  
with 1/2 sacks of cement, 8 lbs.  
of Calcium Chloride. 285 feet  
of 1/2 inch casing set with ~~1/2~~ float shoe.  
topcenterlizer set at 165 feet and  
bottom centerlizer set at 264 feet.