

V W & B DRILLING CO.

Box 7 N. Hwy. 169
CHERRYVALE, KS 67335

Devlin Farm Well #52

Sec. 3 T31S R21E

Drilling began 3-30-80 Completed 4-2-80

Drilled for Hickory Creek Oil Company

Figures indicate the bottom
of the formation

1	Top Soil	1	Streak of Coal	169
6	Gray Clay	7	4 Lt. Shale	173
8	Yellow Clay	15	1 Lime	174
1	River Gravel	16	3 Lt. Shale	177
19	Lime 35	35	3 Med. Shale	180
1	Med. Shale	36	7 Dk. Sandy Shale	187
5	Blk. Shale	41	76 Bartlesville Sand	253
13	Lime	54	Start Core 185	
1	Med. Shale	55	Stop Core 205	
4	Blk. Shale	59	Streak of Coal	253
12	Lt. Shale	71	4 Bartlesville Sand	257
2	Sand Stone	73	14 Med. Shale	271
70	Med. Shale	143	2 Dk. Shale	273
6	Dk. Shale	149	Streak of Coal	273
9	Med. Shale	158	12 Lt. Shale	285
1	Lime	159	6 Med. Shale	291
1	Lt. Shale	160	2 Lt. Shale	293
1	Lime	1616	1 Red Shale	294
8	Lt. Shale	169	7 Grn Shale	301

20 feet of 7 inch casing set with
4 sacks of cement & 10 lbs calcium
chloride. 285 feet of 4 inch casing
set with float shoe. Top centerlizer
set at 165 feet. Bottom centerlizer
set at 252 feet.