

V W & S DRILLING CO.

Box 7 N. Hwy. 169
CHERRYVALE, KS 67335

Devlin Farm Well #56

Drilled for Hickory Creek Oil Company

Sec. 3 T31S R21E

Began Drilling 4-2-80 Completed 4-7-80

Figures indicate bottom
of the formation

1	Top Soil	1	1	Lime	164
6	Gray Clay	7	3	Dk. Shale	167
5	Yellow Clay	12	8	Lt. Shale	175
4	River Gravel	16	6	Streak of Coal	175
20	Lime	36	6	Lt. Shale	181
6	Blk. Shale	42	16	Med. Shale-Sandy	197
1	Lt. Shale	43	25	Bartlesville Sand	222
14	Lime	57		Start Core	197
5	Blk. Shale	62		Stop Core	217
9	Lt. Shale	71	16	Broken Sand & Shale	238
2	Sand Stone	73	27	Med. Shale	265
3	Sandy Shale	76	7	Dk. Shale	272
70	Med. Shale	146		Streak of Coal	272
2	Dk. Shale	148	9	Lt. Shale	281
3	Med. Shale	151	7	Med. Shale	288
	Streak of Coal	151	3	Grn Shale	291
10	Med. Shale	161	1	Red Shale	292
1	Lt. Shale	162	9	Grn. Shale	301
1	Dk. Shale	163			
1					

20 feet of 7 inch casing set with
5 sacks of cement and 10 lbs. of
calcium choloride. 285 feet of
4 inch set with float shoe. Top
centerlizer set at 186 feet. Bottom
centerlizer set at 252 feet.