

V W & B DRILLING CO.
Box 7 N. Hwy. 169
CHERRYVALE, KS 67335

Devlin Farm Well #36

Sec. 3 T31S R21E
Loc. SE of NW 2000
feet from west line.
2230 feet from North
line.

Began Drilling 2-22-80 Completed 2-25-80

Drilled for Hickory Creek Oil Company

Figures indicate the bottom
of the formation

1	Top Soil	1	2	Lime	163
17	Yellow Clay	18	6	Blk. Shale	169
1	River Gravel	19	9	Lt. Shale	178
17	Lime	36	11	Dk. Shale	189
1	Med. Shale	37		Start Core	189
5	Blk. Shale	42	1	Lt. Shale	190
1	Med. Shale	43		Bartlesville Sand	
12	Lime	55		Stop Core	209
5	Blk. Shale	60	59	Bottom of Sand	249
12	Lt. Shale	72	26	Med. Shale	275
77	Med. Shale	149	7	Lt. Shale	282
8	Dark Shale	157	5	Med. Shale	287
1	Lime	158	14	Lt. Shale	301
3	Lt. Shale	161			

21 feet of 7 inch casing set with
5 sacks of cement, 10 lbs Calcium
Choloride. 285 feet of 4 inch
casing set. Top centerlizer 186feet.
Bottom centerlizer set at 252 feet
with float shoe.