

V W & B DRILLING CO.
Box 7 N. Hwy. 169
CHERRYVALE, KS 67335

Devlin Farm Well #40

Sec. 3 T31S R21E
Loc. SE of NW
1760 feet from West Line
2560 feet from North line.

Drilling Began 2-19-80 Completed 2-22-80

Drilled for Hickory Creek Oil Company

Figures indicate the bottom of
the formation

1	Top Soil	1	5	Med. Shale	156
5	Yellow Clay	6		Streak of Coal	156
6'	River Gravel	12	3	Med. Shale	159
15	Lime	27	9	Lt. Shale	168
5	Blk. Shale	32		Top of Sand	
1	Lt. Shale	33		Start Core	168
14	Lime	47		Stop Core	208
3	Blk. Shale	50	81	Bartlesville Sand	249
12	Lt. Shale	62	1	Coal	250
74	Med. Shale	136	11	Sand	261
	Streak of Coal	136	9	Med. Shale	270
3	Lt. Shale	139	9	Lt. Shale	279
10	Med. Shale	149	4	Med. Shale	283
2	Lime	151	18	Lt. Shale	301

20 feet of 7 inch casing set with
5 sacks of cement, 10 lbs Calcium
Choloride. 285 feet of 4 inch
casing set with top centerlizer set
at 165 feet. Bottom centerlizer
set at 264 feet with float shoe.