

VW & B DRILLING CO.
Box 7 N. Hwy. 169
CHERRYVALE, KS 67335

Devlin Farm Well # 50

Sec. 3 T31S R21E
Loc. 1

Began Drilling 3-7-80 Completed 3-18-80

Drilled for Hickory Creek Oil Company

Figures indicate the bottom on the
Formation

1	Top Soil	1	4	Lt. Shale	172
7	Gray Clay	8	10	Sand Stone	182
6	Yellow Clay	14	8	Med. Shale	190
1	River Gravel	15		Start Core	182
21	Lime	36		Stop Core	242
1	Lt. Shale	37	31	Bartlesville Sand	221
4	Blk. Shale	41	3	Med. Shale	224
1	Med. Shale	42	1	Sand Stone	225
13	Lime	55	2	Med. Shale	227
5	Blk. Shale	60	1	Sand Stone	228
1	Med. Shale	61	3	Med. Shale	231
1	Lime	62	8	Dk. Sand Stone	239
6	Lt. Shale	68	31	Med. Shale	270
5	Sand & Shale	73	3	Lt. Shale	273
73	Med. Shale	146		Streak of Coal	273
5	Dk. Shale	151	6	Lt. Shale	279
8	Med. Shale	159	6	Med. Shale	285
3	Lt. Shale	162	4	Lt. Shale	289
2	Lime	164	1	Red. Shale	290
4	Dk. Shale	168	11	Lt. Shale	301

21 feet of 7 inch casing set with
5 sacks of cement & 10 lbs. of
calcium choloride. 289 feet of
4 inch casing set with float shoe.
Top centerlizer set at 157 feet.
Bottom centerlizer set at 256 feet.