


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- BRINEGAR-BROWNLEE-ALCOCK
Farm- A. G. Fuhlhage No. 7

SEC. 27 T. 25 R. 11E
CNE SW

Total Depth. 1490'6"
Comm. 6-29-50 Comp. 7-20-50
Shot or Treated.
Contractor. Brownlee & Alcock Drlg.
Issued. 2-9-52

County Woodson
KANSAS



Elevation. 1065

Production. 40 bbls

CASING:

12 1/2"	11'6" P.
10 "	168'6" P.
5 5/8"	856' P.
7"	1428'6" P.
soil, clay	10
lime	22
shale	38
lime	41
shale	55
lime	58
shale sandy	130
sand 3 BW	155
shale	180
lime	185
shale	190
lime	195
shale	366
lime	418
shale	423
lime	557
3 BW @ 590	
shale, lime, shells	590
lime	640
HPW @ 640	
shale	645
lime	655
shale	659
lime	667
shale	690
lime	767
shale	769
lime	772
shale dark	775
lime	848
shale	994
lime	997
shale	1025
lime	1044
shale	1127
lime	1147
shale	1162
lime	1169
shale	1171
lime	1183
shale dark	1200
shale light	1218
sand squirrel S.O.	1240
shale	1276
lime	1279
shale sandy	1385
shale dark	1426
Free oil showing @ 1419	
Steel line run @ 1419 O.K.	
shale light	1428'6"
sand, shale Oil Showing	1440
shale sandy	
No oil inc.	1445'6"
shale sandy	1450'6"
good sand gas & oil	1456
sand oil increase	
some shale, showing	1461
shale light sandy	1466

Figures Indicate Bottom of Formations.

about the same formation.
1471
sand brown rather
hard Gas & Oil
increase 1476 1/2
sand brown shale at
the bottom of run 1481 1/2
shale dark 1490'6"
Total Depth

Tops: Scout.
Bartlesville 1450

Natural production--18 bbls

Shot: 40 qts 1450-1459
40 " 1470-1479
80 "

Production after shot: 40 bbls

7-21-50 4 PM to 8 PM
Test 16 hrs 7-22-50
260' fluid -- 1 BW from
formation.