

State Kansas County Barton


Company GMR Oil Co. Well No. 1

Farm Steckel

Survey _____

Block No. _____ Sec. 32 Twp. 19S Range 12W

Co-Ord. _____ Elev. 1816 DF
SE SE NE 1819 KB



FT. ZARAH

GMR

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
		SPD 10-9-51
10-10		8 5/8" @ 150' w/150 sx
	622	Anhydrite (+1197)
	1100	Drlg
10-11	2061	Drlg
10-12	2281	Drlg
10-13	2825	Drlg
10-14	3030	Drlg
	2987	Heebner
	3102	Brn Ls

706062

Date	Depth	
	3119	Lansing (-1300)
10-15	3258	Drlg
10-16	3358	Congl
	3367	Arbuckle (-1548)
	3373	R.T.D.
10-16		Sj 5½" @ 3369
10-26	3373	D.P. S/D
	3379	D.D. 1000 Acid 1500# to 600 in 40".
10-27		Swb 21 B0/13 hrs
	3386	D.D. (-1567) Swb 2-3 BOPH 2000 acid
10-28		Swb 51 B0/10 hrs
11-28		State Phy Potential 80.73
*** SEE BELOW		
1-28-52		Pb to 3369 (Pressure-2700#)
1-29		DOC to 3375 S/O
1-30	3378	D.D. 1500 Acid 1100#. Swb 10 GO & 10 GW (Acid?)

1-1-52	3386	Swb 1 BOPH. (Set plug @ 3360)
1-2		Perf 3344-47 w/9 shots
		" 3315-19 w/12 shots
		" 3265-69 w/12 shots
		" 3246-50 w/12 shots

State Kansas County Barton

Company GMR Oil Co. Well No. 1


Farm Steckel

Survey _____

Block No. _____ Sec. 32 Twp. 19S Range 12W

Co-Ord. _____ Elev. 1819 KB

SE SE NE



Page 2

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
1-4-52		1000 Acid 3344-47 N.S.
		1000 Acid 3315-19
		Swb $3\frac{1}{2}$ BOPH & 3 BWPH
		Depleted and plugged 10-26-53
10-26-53		Recovered 2800' $5\frac{1}{2}$ "