

*Plotted over
6-16-13W*

CITIES SERVICE OIL CO.
Bauman No. 6

SEC. 6 T. 16 R. 13W.
CWL E $\frac{1}{2}$ SW
1336' South 970' West of
Center.

Total Depth. 3344
Comm. 9-21-40 Comp. 10-8-40
Shot or Treated.
Contractor. Corbett-Barbour Drlg. Co.
Issued. 11-16-40

County Barton.



CASING.

65/8" 347' Cemented.
5 $\frac{1}{2}$ " 3335' Cemented.

Elevation.

Production. Pot. 5466 B.

Figures Indicate Bottom of Formations. no wtr. Echometer.

surface clay and sand	336
red rock	347
shale shells and iron	415
shale	465
sand	495
red rock	750
shale and red bed	862
anhydrite	906
red rock	930
shale and shells	1210
shale and salt	1300
salt	1450
shale and shells	1520
shale	1715
shale and broken lime	1800
broken lime	1915
lime	1983
broken lime	2056
lime	2214
broken lime and shale	2288
lime	2356
broken lime	2434
broken lime and shale	2518
shale and shells	2724
shale	2795
lime	2857
broken lime and shale	2932
lime	3039
lime broken	3147
lime	3336
Rotary total depth 3336 equals 3336 SLM.	
Arbuckle	3344

Total Depth.

Top Arbuckle 3334
Penetration 10'

FILLUP

900' oil in 1 $\frac{1}{2}$ hours.
1800' oil in 2 $\frac{1}{2}$ hours.
2200' oil in 3 $\frac{1}{2}$ hours.
2600' oil in 5 $\frac{1}{2}$ hours.