

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas


6-16-13W

PHILLIPS PETRO.CO.
H.Bitter No. 8.

SEC.6 T.16 R.13W
CW $\frac{1}{2}$ SW NE

Total Depth. 3350' DF
Comm. 9-25-40 Comp. 11-6-40
Shot or Treated.
Contractor.
Issued. 2-15-41

County. Barton



CASING:
8" 612'
5" 3339'

Elevation.

Production. Pot.1688 B.
Deptho.

Figures Indicate Bottom of Formations.

surface clay & sand	70
sand shale & pyrite	415
sand & shale	615
shale & shells	763
shale & shells	884
anhydrite	920
shale & shells	1093
shale & salt	1315
shale & shells	1625
shale & lime shells	1951
lime	2088
shale sticky	2120
shale	2179
shale & shells	2410
shale & shells	2720
lime	2857
shale & lime	2910
lime	3032
shale & lime	3069
lime	3120
lime sft porous	3153
shale & lime	3228
lime	3335
shale	3338
lime	3350
Total Depth-Derrick Floor	

Tops

Kansas City	3093
porous but not sat.	3116-45
Arbuckle	3339
saturation in cuttings	
cored 3340-50 sat. & por.	

500 & 2000 Gals .Acid