

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bank Bldg, Wichita, Kansas.

PLOTTED
J.E. Jameson
6-16-13W

THE TEXAS COMPANY,
L. Hoffman No. 5

SEC. 6 T. 16 R. 13 W.
SE NW NW
990' fr N and W.L. NW $\frac{1}{4}$

Total Depth. 3340
Comm. 10-16-37 Comp. 11-13-37 DEC 18 1937
Shot or Treated. 1000 gal acid.
Contractor. Parker Drlg. Co.
Issued. 12-18-37

County Barton.

CASING. Rotary 3323'
Cable 3340'

10" 352'
7" 3322'



Elevation.

Production. Pot. 2441 B.

Figures Indicate Bottom of Formations.

shale and lime shells	255
shale and shells	560
red rock and shale	750
shale and shells	862
anhydrite	895
shale and shells	985
red rock	1009
shale and shells	1320
salt	1515
shale and shells	1570
broken shale and lime	1645
lime and paratise	1714
shale and shells	1825
broken lime	1870
lime	1975
broken lime	2075
lime	2175
broken lime and strks of shale	2212
shale and lime shells	2295
broken lime and shale	2375
shale	2515
shale and lime	2588
shale and shells	2727
lime and shale	2840
lime	2933
gyp and lime	2965
broken lime	2970
lime	3333
lime grey	3337
lime	3340
Total Depth.	