


SACO OIL CO.-O.J.CONNELL.
Klick No. 1

SEC. 20 T. 25 R. 14E.
SW NW SW
1020' S of N.L.
330 E of W.L. SW $\frac{1}{4}$
County. Woodson.

Total Depth. 1436
Comm. 6-7-35 Comp. 7-6-35.
Shot or Treated. 80 qts 1391-1434
Contractor. J.D. Ladd.
Issued. 8-10-35.

CASING.

10" 80'
8 $\frac{1}{2}$ " 607'
65/8" 1070'
53/16" 1378'



Elevation.

Production. 564 B. 24 Hr.

Figures Indicate Bottom of Formations

soil	2	shale	1080
lime	16	lime hard	1082
shale blue	26	lime	1085
lime	31	shale	1088
shale light	34	lime	1097
sand water	68	shale	1107
shale	155	lime	1110
lime	158	shale blue	1113
shale	160	lime	1114
lime	169	shale	1117
shale light	196	lime	1119
shale blue	335	shale	1125
lime	385	lime	1130
shale light	388	shale	1135
lime hard	395	lime hard	1145
lime	538	shale dark	1155
shale light	551	shale light	1157
lime	572	lime	1162
sand water	591	shale light	1240
lime	618	lime	1243
lime sdy	635	shale sdy	1272
lime	646	shale blue	1284
shale light	664	shale light	1295
lime	715	shale dark	1307
lime soft	730	shale light	1320
lime hard	760	shale dark	1340
shale	763	shale blk	1352
lime	820	shale grey sdy	1370
shale blue	825	sand scum of oil and gas	1381 GAS.
shale sdy	920	sand oil show first	1391
shale blue muddy	940	oil Increase	1400
lime	946	oil sand	1410
shale	958	shale	1414
lime	961	oil sand	1436
shale	975	Total Depth.	
lime	977		
shale white	988	WATER RECORD.	
lime hard	1005		
shale	1012	HFW 68'	
lime	1015	HFW 572-591	
shale white	1027	5 BWPH 715-730	
lime	1029	HFW 1035	
shale	1035		
sand	1065		
shale	1075		
lime blk	1076		