

THE SACO OIL COMPANY.  
 Klick No. 2


SEC, 20 T. 25 R. 14E.  
 NE SW SW

Total Depth, 1438  
 Comm. 10-21-35 Comp. 11-7-35.  
 Shot or Treated, 160 qts 1393-1436  
 Contractor, The Saco Oil Co.  
 Issued, 12-14-35

County, Woodson.

CASING.

12 1/2" 110' 65/8" 1370'  
 10" 635 53/16" ~~1393'~~ 1438'  
 8 1/2" 1132'



Elevation.

Production. 200 bbls.,

Figures Indicate Bottom of Formations.

lime	10	shale	1230
shale	45	lime	1240
shale sdy	65	shale	1320
sand water	75	lime	1325
slate blue	108	shale dark	1330
shale blue	145	shale grey	1340
lime	160	shale blk	1350
shale	185	shale grey	1364
lime	190	shale sdy	1383
shale	330	sand grey	1387
lime	440	sand	1389 SIM
shale white	445	sand gas fluffy	1393
lime	620	sand coarse	1401
shale	633	sand brown	1411
lime	635	sand brown	1420
lime broken and slate	645	sand white and coarse.	1427
lime	665	sand white .	1432
shale	668	sand	1438
lime	810	Total Depth.	
shale	820		
shale blue	825	<u>WATER RECORD.</u>	
shale white	845	8 BW 65'	
lime	855	10 BWPHR 560-75	
shale white	975	HFV 585	
lime	990	1 BW 720	
shale white	1005	1 BW 750	
lime broken	1022	3 BW 1022-48	
sand	1040		
shale	1054	<u>OIL &amp; GAS SHOWS.</u>	
lime	1059	scum oil 1375	
shale	1061	Gas 1388	
lime	1105	gas 1393	
shale	1115	First oil 1393	
lime	1150	First free oil 1400	
shale	1220	flowed and cleaned sdf 1415	
lime	1222	flowing nat at 10 BPH 1439	

shot from 1393 to 1436 with 160 qts  
 and 100' of sand with 65/8 out and  
 hole full of water.