

21-16-12W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

503 East Murdock,

Wichita, Kansas

Company- DUKE DRILG. CO.

Farm- Stoskopf

No. 1

SEC. 21 T. 16 R. 12W
NE SW SE

Total Depth. 3420'

Comm. 3-1-57


Shot or Treated.

Contractor.

Issued. 10-12-57

Comp. 3-12-57

County Barton
KANSAS



Elevation. 1919 KB

Production. 25 BOPD

CASING:

8 5/8" 301'
5 1/2" 3420'

Figures indicate Bottom of Formations.

surface clay	30
shale-rock	80
sand	90
shale	110
sand	120
shale	270
sand	285
shale	310
sand	325
shale	530
red bed	814
Anhydrite	838
shale-shell	1225
salt-shale	1400
shale-shell	1690
lime	1885
brkn lime	2005
lime-shale	2705
lime	2997
Heebner	3060
lime	3101
Lansing	3180
lime	3364
Arbuckle	3420
Total Depth	

TOPS:

Anhydrite	814
Howard	2678
Topeka	2716
Heebner	2997
Toronto	3016
Douglas	3032
Iatan	3083
Lansing	3101
Conglomerate	3346
Arbuckle	3364