


THE SACO OIL CO.  
 Klick No. 6

SEC. 20 T. 25 R. 14E.  
 NW SW SW

49195

Total Depth. 1450  
 Comm. 9-19-37 Comp. 9-29-37  
 Shot or Treated. 110 qts 1400-1425  
 Contractor. The Saco Oil Co.  
 Issued. 10-30-37

County Woodson.



CASING.

12 1/2" 80'  
 10" 615'  
 8 1/4" 1094'  
 6 5/8" 1385'

Elevation.

Production. DRY.

Figures Indicate Bottom of Formations.

clay	5	lime	1150
lime	18	shale	1155
shale	60	lime	1165
water sand	75	shale	1240
shale	158	lime	1243
lime	160	shale blk	1260
shale	162	shale	1265
lime	170	limo.	1275
shale light	235	shale light	1335
shale	345	shale dark	1382
lime	383	sand grey hard	1385
shale	395	shale sdy dark	1395
lime	495	shale sdy light	1400
lime hard	525	sand muddy	1410
lime	535	sand coarse	1418
lime shells	560	shale break	1420
limo sdy	565	shale sdy dark	1440
limo soft	605	shale blk	1450
lime hard	620		
lime sdy	635	Total Depth.	
shale	640		
lime	650	Plugged back from 1450 to 1425	
shale	675	shot from 1400 to 1425 with 110 qts	
lime	750	5 gal water and 7 gal oil on	
shale blk	753	32 hour test. plugged and abd.	
lime	820		
slate blk	823		
shale	945		
lime	950		
shale	965		
lime	975		
shale	995		
lime	1015		
shale	1045		
shale sdy	1065		
shale	1075		
limo	1077		
shale blk	1080		
lime	1082		
lime hard	1088		
shale	1093		
lime	1094		
shale	1130		

WATER RECORD.

HFV	65-75
HFV	580-600
2 BWPHR	675
1 BWPHR	820-822
3 BWPHR	1045-1070

OIL SHOW.

Show oil 1412.