

VW & B DRILLING CO.  
 Box 7 N. Hwy. 109  
 CHERRYVALE, KS 67335

Wamsley Farm Well # 7

Sec. 16 T31S R21E  
 NE $\frac{1}{4}$   
 County: Labette

Drilled for Hickory Creek  
 Commenced Drilling 9-25-80  
 Completed Drilling 9-9-29-80

Figures indicate the bottom  
 of the formation

1	Top Soil	1	28	Dk. Shale	178
4	Brn Clay	5		Start Core 161'	
8	Yellow Clay	13		Stop Core 201'	
2	River Gravel	15	6	Sandstone	184
13	Lime	28	1	Gray Shale	185
4	Blk. Shale	32	12	Sandstone	197
4	Lime	36	1	Coal	198
6	Sandstone	42	1	Lime	199
2	Lt. Shale	44	1	Coal	200
4	Gray Shale	48	2	Gray Shale	202
2	Sandstone	50	1	Coal	203
80	Gray Sandy Shale	130	10	Lt. Shale	213
2	Dk. Shale	132	3	Sandstone	216
1	Lime	133		Start core 216'	
1	Coal	134		Stop Core 236'	
15	Gray Shale	149	36	Gray Shale	252
1	Lt. Shale	150	8	Lt. Shale	260
			9	Gray Shale	269
			17	Lt. Shale	286
			8	Gray Shale	294
			7	Dk. Shale	301

Hole size 6 $\frac{1}{2}$ "  
 20 feet of 7" casing set with 5 sacks  
 of cement 10 lbs. calcium chloroxide.  
 283'3" of 4 inch casing set with float  
 shoe. Bottom centerlizer set at 231'  
 Top centerlizer set at 132'.