

CITIES SERVICE OIL CO.
Bitter No. 1-C

18-16-13W
SEC. 18 T. 16 R. 13W
NWc NE
330'S 330'E of N/4 Cor.


Total Depth. 3389'
Comm. 11-21-37 Comp. 12-18-37
Shot or Treated. 2000 Gals.
Contractor. R.W. Rine Drlg. Co.
Issued. 1-29-38

County. Barton

CASING:

10" 413'
7" 3373' SLM

JAN 29 1938



Elevation.

Production. Pot. 518 B.
1 1/2% wtr.

Figures Indicate Bottom of Formations.

surface clay & sand	70
surface sand, clay, shale & shells	240
shale & shells	413
shale	484
shale, shells, iron & red bed	700
shale, shells & anhydrite	1005
shale & shells	1395
salt, shale & shells	1625
salt, shale & gyp	1793
shale & shells	1920
shale & lime	2008
brkn lime	2175
shale & lime	2235
shale & lime shells	2288
shale & lime	2329
shale & shells	2405
shale & lime shells	2545
shale & shells	2615
brkn lime	2721
shale & lime	2770
lime	3053
shale & lime shells	3119
shale & lime	3134
oolitic lime (porous (cored))	3149
lime	3197
shale	3215
lime (cored)	3225
lime	3279
shale & lime	3319
lime	3360
lime (cored)	3362
lime & shale (cored)	3373
lime	3389
Total Depth.	

Top Siliceous 3372 SLM
Pen 17'
T.D. 3389'